CASE STUDY



Location: Toowoomba

Client: Queensland Department of Education and

Training

Duration: 3 months

DESCRIPTION

Joe Wagner Group was appointed principal contractor for the construction of a new staff carpark.

Works included:

- Bulk earthworks and subgrade treatment
- Unbound pavements
- Installation of pre-cast concrete drainage pipes and structures
- Cast in-situ concrete works including footpath and crossover pavement
- Design and construction of retaining wall and 3.5m high fencing attached to the wall (6m high total)
- Asphalt, line marking, signage
- Installation of discus/shotput structures including pouring of slab and erection of fencing
- Landscaping and turf

JWG and our subcontractors found a solution for limited space by designing a combined fence and retaining wall structure. Working on a Department of Education and Training facility required stringent attention to safety due to the presence of students and staff on the school grounds.

The project was completed within a tight time-frame so that client could commence with another building project; with no LTIs.

















